



Yorktown

Blocks 39-44

P.U.D. 61 Amended "C"

A SUBDIVISION IN THE CITY OF JENKS, TULSA COUNTY, OKLAHOMA BEING A PART OF THE WEST HALF OF THE SOUTHEAST QUARTER (W/2 SE/4) OF SECTION SIX (6), TOWNSHIP SEVENTEEN (17) NORTH, RANGE THIRTEEN (13) EAST OF THE INDIAN BASE AND MERIDIAN.

Owner / Developer

YORKTOWN HOLDING, LLC.
5711 EAST 71ST STREET, SUITE 120
TULSA, OKLAHOMA 74136
PHONE: (918) 494-4004
MR. STEVE MURPHY

Engineer

COWAN GROUP ENGINEERING, LLC
5416 SOUTH YALE AVENUE, SUITE 210
TULSA, OKLAHOMA 74135
PHONE: (918) 949-6171
FAX: (918) 949-6174
barrick@cowangroup.co
C.A. # 6414 EXPIRES 6-30-2018

Surveyor

FRITZ LAND SURVEYING, LLC
2017 WEST 91ST STREET
TULSA, OKLAHOMA 74132
PHONE: (918) 231-0575
fritzlandsurveying@gmail.com
C.A. # 5848 EXPIRES 6-30-2017

Subdivision Statistics

SUBDIVISION CONTAINS ONE HUNDRED AND FIVE (105) LOTS IN SIX (6) BLOCKS AND FOUR (4) RESERVE AREAS:

BLOCK 39	5 LOTS
BLOCK 40	10 LOTS
BLOCK 41	42 LOTS
BLOCK 42	10 LOTS
BLOCK 43	22 LOTS
BLOCK 44	16 LOTS

GROSS SUBDIVISION AREA:
1,512,772.72 SF / 34.728 ACRES

Basis of Bearings

ASSUMED USING THE SOUTH LINE OF THE SOUTHEAST QUARTER (SE/4) OF SECTION SIX (6), TOWNSHIP SEVENTEEN (17), RANGE THIRTEEN (13) AS N 88°36'57" E.

Monumentation



ALL CORNERS SHOWN HEREON WERE SET USING A 3/8" x 18" STEEL PIN WITH A GREEN PLASTIC CAP STAMPED "FRITZ CA5848".

Curve Table

CURVE	ARC LENGTH	RADIUS	DELTA ANGLE	CHORD BEARING	CHORD LENGTH
C1	211.02'	175.00'	69°05'23"	N 35°28'13" W	198.47'
C2	39.36'	25.00'	90°12'36"	S 24°54'36" E	35.42'
C3	39.18'	25.00'	89°47'24"	N 85°05'24" E	35.29'
C4	142.09'	300.00'	27°08'16"	S 56°26'46" E	140.77'
C5	65.32'	350.00'	10°41'32"	S 48°13'25" E	65.22'
C6	58.29'	28.00'	119°17'16"	S 50°20'28" W	48.32'
C7	57.17'	28.00'	118°59'00"	N 04°55'19" E	47.74'
C8	220.54'	50.00'	252°43'00"	S 62°56'40" E	80.53'
C9	150.73'	125.00'	69°05'23"	N 35°28'13" W	141.76'
C10	39.27'	25.00'	90°00'00"	N 44°04'29" E	35.36'
C11	117.92'	300.00'	22°31'17"	S 77°48'50" W	117.16'
C12	98.27'	250.00'	22°31'17"	S 77°48'50" W	97.64'
C13	39.27'	25.00'	90°00'00"	N 45°55'31" W	35.36'
C14	39.27'	25.00'	90°00'00"	N 44°04'29" E	35.36'
C15	110.63'	250.00'	25°21'15"	S 76°23'52" W	109.73'
C16	91.73'	200.00'	26°16'46"	N 76°51'37" E	90.93'
C17	21.03'	25.00'	48°11'23"	S 65°54'19" E	20.41'
C18	241.19'	50.00'	276°22'46"	S 00°00'00" E	66.67'
C19	21.03'	25.00'	48°11'23"	S 65°54'19" W	20.41'
C20	69.14'	250.00'	15°50'47"	N 82°04'37" E	69.92'
C21	34.72'	25.00'	79°34'01"	N 66°03'46" W	31.99'
C22	88.50'	200.00'	25°21'15"	N 13°36'08" W	87.78'
C23	21.03'	25.00'	48°11'23"	N 23°10'10" E	20.41'
C24	163.05'	50.00'	186°50'18"	S 46°09'17" E	99.82'
C25	21.03'	25.00'	48°11'23"	S 64°31'16" W	20.41'
C26	21.03'	25.00'	48°11'23"	N 67°17'22" W	20.41'
C27	162.25'	50.00'	185°55'14"	N 43°50'43" E	99.87'
C28	21.03'	25.00'	48°11'23"	S 25°01'12" E	20.41'
C29	39.27'	25.00'	90°00'00"	S 44°04'29" W	35.36'
C30	39.27'	25.00'	90°00'00"	N 45°55'31" W	35.36'
C31	88.50'	200.00'	25°21'15"	S 76°23'52" W	87.78'
C32	39.27'	25.00'	90°00'00"	S 18°43'14" W	35.36'
C33	110.63'	250.00'	25°21'15"	N 13°36'08" W	109.73'
C34	39.47'	25.00'	90°27'32"	S 46°09'17" E	35.50'
C35	39.07'	25.00'	89°32'28"	N 43°50'43" E	35.21'
C36	39.27'	25.00'	90°00'00"	S 44°04'29" W	35.36'
C37	39.27'	25.00'	90°00'00"	N 45°55'31" W	35.36'
C38	39.07'	25.00'	89°32'28"	N 43°50'43" E	35.21'
C39	39.47'	25.00'	90°27'32"	S 46°09'17" E	35.50'
C40	39.27'	25.00'	90°00'00"	S 45°55'31" E	35.36'


Line Table

LINE	BEARING	DISTANCE
L1	S 20°11'42" W	198.80'
L2	S 70°00'54" E	118.27'
L3	S 20°11'42" W	198.43'
L4	S 70°00'54" E	71.72'
L5	N 70°00'54" W	272.33'
L6	N 89°04'29" E	63.56'
L7	S 89°04'29" E	479.87'
L8	N 89°04'29" E	189.87'
L9	N 00°55'31" W	210.00'
L10	N 89°04'29" E	132.37'
L11	N 63°43'14" E	100.40'
L12	N 00°00'00" E	61.66'
L13	N 00°00'00" W	61.66'
L14	N 26°16'46" W	89.06'
L15	N 00°55'31" W	91.62'
L16	S 88°36'57" W	468.22'
L17	S 00°55'31" E	316.48'
L18	S 89°04'29" W	95.00'
L19	N 89°04'29" E	132.37'
L20	N 63°43'14" E	50.20'
L21	N 26°16'46" W	84.51'
L22	N 00°55'31" W	97.12'
L23	S 88°36'57" W	190.01'
L24	N 00°55'31" E	328.08'
L25	S 89°04'29" E	637.28'
L26	S 89°04'29" W	190.00'
L27	N 00°55'31" W	635.76'
L28	N 88°36'57" E	190.01'
L29	N 89°04'29" E	95.00'
L30	S 00°55'31" E	376.54'



Location Map

SCALE: 1"=200'



Scale: 1" = 100'

FINAL PLAT

CERTIFICATE OF APPROVAL

I HEREBY CERTIFY THAT THIS PLAT WAS APPROVED BY THE JENKS CITY COUNCIL ON

AUGUST 17, 2015
Keely Chalkley
MAYOR - VICE MAYOR

THIS APPROVAL IS VOID IF THE ABOVE SIGNATURE IS NOT ENDORSED BY THE CITY MANAGER.

CITY MANAGER

STATE OF OKLAHOMA)
COUNTY OF TULSA)

I, PAT KEY, TULSA COUNTY CLERK, IN A FOR THE COUNTY AND STATE ABOVE NAMED, DO HEREBY CERTIFY THAT THE FORGOING IS A TRUE AND CORRECT COPY OF A LIKE INSTRUMENT NOW ON FILE IN MY OFFICE.

DATED THE _____ DAY OF _____, 2016
PAT KEY, TULSA COUNTY CLERK

DEPUTY

CERTIFICATE

I hereby certify that all real estate taxes involved in this plat have been paid as reflected by the current tax rolls. Security as required has been provided in the amount of \$14,144.00 per trust receipt no.14615 to be applied to 2016 taxes. This certificate is NOT to be construed as payment of 2016 taxes in full but is given in order that this plat may be filed on record. 2016 taxes may exceed the amount of the security deposit.

Dated: 10/05/2016
Dennis Semler
Tulsa County Trustee
By: *[Signature]*
Deputy

Deed of Dedication
YORKTOWN BLOCKS 39-44
PUD #61 Amended "C"

KNOW ALL MEN BY THESE PRESENTS:

YORKTOWN HOLDING, L.L.C., AN OKLAHOMA LIMITED LIABILITY COMPANY, HEREINAFTER REFERRED TO AS THE OWNER, IS THE OWNER OF THE FOLLOWING DESCRIBED LAND IN THE CITY OF JENKS, TULSA COUNTY, STATE OF OKLAHOMA, TO-WIT:

A PART OF THE WEST HALF OF THE SOUTHEAST QUARTER (W/2, SE/4) OF SECTION SIX (6), TOWNSHIP SEVENTEEN (17) NORTH, RANGE THIRTEEN (13) EAST OF THE INDIAN BASE AND MERIDIAN, CITY OF JENKS, TULSA COUNTY, STATE OF OKLAHOMA, ACCORDING TO THE U.S. GOVERNMENT SURVEY THEREOF.

MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHWEST CORNER OF SAID SOUTHEAST QUARTER; THENCE N 88°36'57" E, ALONG THE SOUTH LINE OF SAID SOUTHEAST QUARTER (SE/4), A DISTANCE OF 113.29, TO THE POINT OF BEGINNING; THENCE N 01°00'32" W A DISTANCE OF 522.99 FEET; THENCE N 20°47'02" E A DISTANCE OF 237.50 FEET; THENCE N 00°00'00" E A DISTANCE OF 102.54 FEET; THENCE N 90°00'00" E A DISTANCE OF 134.49 FEET, TO A TANGENT POINT OF CURVATURE; THENCE ALONG A CURVE TO THE LEFT HAVING A RADIUS OF 300.00 FEET, A CENTRAL ANGLE OF 35°05'48", AN ARC DISTANCE OF 183.77 FEET, A CHORD BEARING OF N 72°27'06" E AND A CHORD DISTANCE OF 180.91 FEET, TO A TANGENT POINT OF REVERSE CURVATURE; THENCE ALONG A CURVE TO THE RIGHT HAVING A RADIUS OF 250.00 FEET, A CENTRAL ANGLE OF 11°39'00", AN ARC DISTANCE OF 60.83 FEET, A CHORD BEARING OF N 60°43'42" E AND A CHORD DISTANCE OF 50.75 FEET; THENCE N 23°26'48" W A DISTANCE OF 50.00 FEET; THENCE N 00°00'00" E A DISTANCE OF 309.55 FEET; THENCE N 47°07'21" E A DISTANCE OF 222.27 FEET, TO A NON-TANGENT POINT OF CURVATURE; THENCE ALONG A CURVE TO THE RIGHT HAVING A TANGENT BEARING OF N 42°52'39" W, A RADIUS OF 300.00 FEET, A CENTRAL ANGLE OF 22°31'41", AN ARC DISTANCE OF 117.96 FEET, A CHORD BEARING OF N 31°36'48" W AND A CHORD DISTANCE OF 117.20 FEET, TO A POINT OF TANGENCY; THENCE N 20°20'57" W A DISTANCE OF 72.47 FEET; THENCE N 76°00'58" E A DISTANCE OF 235.89 FEET; THENCE S 19°59'02" E A DISTANCE OF 35.66 FEET; THENCE S 39°44'35" E A DISTANCE OF 121.31 FEET; THENCE S 69°48'18" E A DISTANCE OF 169.67 FEET; THENCE S 58°56'07" E A DISTANCE OF 276.45 FEET, TO A POINT ON THE EAST LINE OF THE WEST HALF OF SAID SOUTHEAST QUARTER (W/2, SE/4); THENCE S 00°55'31" E, ALONG THE EAST LINE OF SAID WEST HALF OF THE SOUTHEAST QUARTER (W/2, SE/4), A DISTANCE OF 1324.76 FEET, TO THE SOUTHEAST CORNER OF SAID WEST HALF OF THE SOUTHEAST QUARTER (W/2, SE/4); THENCE S 88°36'57" W, ALONG THE SOUTH LINE OF SAID WEST HALF OF THE SOUTHEAST QUARTER (W/2, SE/4), A DISTANCE OF 1211.89 FEET, TO THE POINT OF BEGINNING.

SAID TRACT OF LAND CONTAINING 34.728 ACRES / 1,512,772.72 SQUARE FEET.

THE BASIS OF BEARINGS FOR SAID TRACT IS N 88°36'57" E, ALONG THE SOUTH LINE OF THE SOUTHEAST QUARTER (SE/4) OF SECTION SIX (6), TOWNSHIP SEVENTEEN (17) NORTH, RANGE THIRTEEN (13) EAST OF THE INDIAN BASE AND MERIDIAN, CITY OF JENKS, TULSA COUNTY, STATE OF OKLAHOMA, ACCORDING TO THE U.S. GOVERNMENT SURVEY THEREOF.

AND HAS CAUSED THE ABOVE DESCRIBED TRACT OF LAND TO BE SURVEYED, STAKED, PLATTED AND SUBDIVIDED INTO 105 LOTS, 6 BLOCKS, 4 RESERVE AREAS, AND STREETS, IN CONFORMITY WITH THE ACCOMPANYING PLAT, AND HAS DESIGNATED THE SUBDIVISION AS "YORKTOWN BLOCKS 39-44", A SUBDIVISION IN THE CITY OF JENKS, TULSA COUNTY, OKLAHOMA.

SECTION I. STREETS, EASEMENTS AND UTILITIES

A. PUBLIC STREETS AND GENERAL UTILITY EASEMENTS

THE OWNER/DEVELOPER DOES HEREBY DEDICATE TO THE PUBLIC THE STREET RIGHTS-OF-WAY AS DEPICTED ON THE ACCOMPANYING PLAT. ADDITIONALLY, THE OWNER DOES HEREBY DEDICATE TO THE PUBLIC THE UTILITY EASEMENTS DESIGNATED AS "UE" OR "UTILITY EASEMENT" FOR THE SEVERAL PURPOSES OF CONSTRUCTING, MAINTAINING, OPERATING, REPAIRING, REPLACING, AND/OR REMOVING ANY AND ALL PUBLIC UTILITIES, INCLUDING STORM SEWERS, SANITARY SEWERS, TELEPHONE AND COMMUNICATION LINES, ELECTRIC POWER LINES AND TRANSFORMERS, GAS LINES, WATER LINES, AND CABLE TELEVISION LINES, TOGETHER WITH ALL FITTINGS, INCLUDING THE POLES, WIRES, CONDUITS, PIPES, VALVES, METERS, AND EQUIPMENT FOR EACH OF SUCH FACILITIES AND ANY OTHER APPURTENANCES THERE TO, WITH THE RIGHTS OF INGRESS AND EGRESS TO AND UPON THE UTILITY EASEMENTS FOR THE USES AND PURPOSES AFORESAID, PROVIDED HOWEVER, THE OWNER/DEVELOPER HEREBY RESERVES THE RIGHT TO CONSTRUCT, MAINTAIN, OPERATE, LAY AND RE-LAY WATER LINES AND SEWER LINES, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS FOR SUCH CONSTRUCTION, MAINTENANCE, OPERATION, LAYING AND RELAYING OVER, ACROSS AND ALONG ALL OF THE UTILITY EASEMENTS DEPICTED ON THE PLAT, FOR THE PURPOSE OF FURNISHING WATER AND/OR SEWER SERVICES TO THE AREA INCLUDED IN THE PLAT. THE OWNER/DEVELOPER HEREIN IMPOSES A RESTRICTIVE COVENANT, WHICH COVENANT SHALL BE BINDING ON EACH LOT OWNER AND SHALL BE ENFORCEABLE BY THE CITY OF JENKS, OKLAHOMA, AND BY THE SUPPLIER OF ANY AFFECTED UTILITY SERVICE, THAT WITHIN THE UTILITY EASEMENTS DEPICTED ON THE ACCOMPANYING PLAT, NO BUILDING, STRUCTURE OR OTHER ABOVE OR BELOW GROUND OBSTRUCTION THAT INTERFERES WITH THE ABOVE SET FORTH USES AND PURPOSES OF AN EASEMENT SHALL BE PLACED, ERECTED, INSTALLED OR MAINTAINED, PROVIDED HOWEVER, NOTHING HEREIN SHALL BE DEEMED TO PROHIBIT DRIVES, PARKING AREAS, CURBING, LANDSCAPING AND CUSTOMARY SCREENING FENCES AND WALLS THAT DO NOT CONSTITUTE AN OBSTRUCTION.

B. UNDERGROUND SERVICE

1. OVERHEAD POLES MAY BE LOCATED ALONG THE SOUTH PERIMETER OF THE SUBDIVISION AS NECESSARY IF LOCATED IN UTILITY EASEMENTS FOR THE PURPOSE OF THE SUPPLY OF UNDERGROUND SERVICE. STREET LIGHT POLES OR STANDARDS MAY BE SERVED BY UNDERGROUND CABLE, AND EXCEPT AS PROVIDED IN THE IMMEDIATELY PRECEDING SENTENCE, ALL ELECTRIC AND COMMUNICATION SUPPLY LINES SHALL BE LOCATED UNDERGROUND IN THE EASEMENT-WAYS RESERVED FOR GENERAL UTILITY SERVICES AND STREETS, SHOWN ON THE ATTACHED PLAT.

2. ALL SUPPLY LINES IN THE SUBDIVISION INCLUDING ELECTRIC, TELEPHONE, CABLE TELEVISION AND GAS LINES SHALL BE LOCATED UNDERGROUND IN THE EASEMENTS RESERVED FOR GENERAL UTILITY SERVICES AND STREETS SHOWN ON THE PLAT OF THE SUBDIVISION. SERVICE PEDESTALS AND TRANSFORMERS, AS SOURCES OF SUPPLY AT SECONDARY VOLTAGES, MAY ALSO BE LOCATED IN THE SAID UTILITY EASEMENTS.

3. UNDERGROUND SERVICE CABLES AND GAS SERVICE LINES TO ALL STRUCTURES WHICH MAY BE LOCATED ON ALL LOTS IN THE SUBDIVISION MAY BE RUN FROM THE NEAREST GAS MAIN, SERVICE PEDESTAL OR TRANSFORMER TO THE POINT OF USAGE DETERMINED BY THE LOCATION AND CONSTRUCTION OF SUCH STRUCTURE AS MAY BE LOCATED UPON EACH SAID LOT, PROVIDED THAT UPON THE INSTALLATION OF SUCH A SERVICE CABLE OR GAS SERVICE LINE TO A PARTICULAR STRUCTURE, THE SUPPLIER OF SERVICE SHALL THEREAFTER BE DEEMED TO HAVE A DEFINITIVE, PERMANENT AND EFFECTIVE EASEMENT ON THE LOT, COVERING A 5 FOOT STRIP EXTENDING 2.5 FEET ON EACH SIDE OF THE SERVICE CABLE, EXTENDING FROM THE SERVICE PEDESTAL, TRANSFORMER OR GAS MAIN TO THE SERVICE ENTRANCE ON THE STRUCTURE OR A POINT OF METERING.

4. THE SUPPLIER OF ELECTRIC, TELEPHONE, CABLE TELEVISION AND GAS SERVICES, THROUGH ITS AUTHORIZED AGENTS AND EMPLOYEES, SHALL AT ALL TIMES HAVE RIGHT OF ACCESS TO ALL SUCH EASEMENTS SHOWN ON THE PLAT OF THE SUBDIVISION OR PROVIDED FOR IN THIS DEED OF DEDICATION FOR THE PURPOSE OF INSTALLING, MAINTAINING, REMOVING OR REPLACING ANY PORTION OF THE UNDERGROUND ELECTRIC, TELEPHONE, CABLE TELEVISION OR GAS SERVICE FACILITIES SO INSTALLED BY IT. THE SUPPLIER OF ELECTRIC, TELEPHONE, CABLE TELEVISION ALSO RESERVE THE PERPETUAL RIGHT, PRIVILEGE, AND AUTHORITY TO CUT DOWN, TRIM, OR TREAT ANY TREES AND UNDERGROWTH ON SAID EASEMENT.

5. THE OWNER OF EACH LOT IN THE SUBDIVISION SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE UNDERGROUND ELECTRIC FACILITIES LOCATED ON HIS PROPERTY AND SHALL PREVENT THE ALTERATION OF GRADE OR ANY CONSTRUCTION ACTIVITY WHICH MAY INTERFERE WITH SAID ELECTRIC, TELEPHONE, CABLE TELEVISION OR GAS FACILITIES. THE SUPPLIER OF SERVICE WILL BE RESPONSIBLE FOR ORDINARY MAINTENANCE OF UNDERGROUND FACILITIES, BUT THE OWNER OF EACH LOT IN THE SUBDIVISION WILL PAY FOR DAMAGE OR RELOCATION OF SUCH FACILITIES CAUSED OR NECESSITATED BY ACTS OF THE OWNER OR HIS AGENTS OR CONTRACTORS. THE FOREGOING COVENANTS CONCERNING UNDERGROUND FACILITIES SHALL BE ENFORCEABLE BY THE SUPPLIER OF ELECTRIC, TELEPHONE, CABLE TELEVISION OR GAS SERVICES.

C. WATER MAINS, SANITARY SEWERS, AND STORM SEWER SERVICES

1. THE OWNER OF EACH LOT SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE PUBLIC WATER MAINS, SANITARY SEWER MAINS AND STORM SEWERS IN THIS ADDITION.

2. WITHIN THE UTILITY EASEMENT AREAS DEPICTED ON THE ACCOMPANYING PLAT, THE ALTERATION OF GRADE FROM THE CONTOURS EXISTING UPON THE COMPLETION OF THE INSTALLATION OF A PUBLIC WATER MAIN, SANITARY SEWER MAIN, OR STORM SEWER MAIN, OR ANY CONSTRUCTION ACTIVITY WHICH WOULD, IN THE JUDGMENT OF THE CITY OF JENKS, INTERFERE WITH PUBLIC WATER MAINS, SANITARY SEWER MAINS AND STORM SEWERS SHALL BE PROHIBITED.

3. THE CITY OF JENKS, OKLAHOMA, OR ITS SUCCESSORS, SHALL BE RESPONSIBLE FOR THE ORDINARY MAINTENANCE OF PUBLIC WATER

MAINS, SANITARY SEWER MAINS AND STORM SEWERS, BUT THE OWNER SHALL PAY FOR DAMAGE OR RELOCATION OF SUCH FACILITIES CAUSED OR NECESSITATED BY ACTS OF THE OWNER, HIS AGENTS OR CONTRACTORS.

4. THE CITY OF JENKS, OKLAHOMA, OR ITS SUCCESSORS, SHALL AT ALL TIMES HAVE RIGHT OF ACCESS TO ALL EASEMENTS DEPICTED ON THE ACCOMPANYING PLAT, OR OTHERWISE PROVIDED FOR IN THE DEED OF DEDICATION, FOR THE PURPOSE OF INSTALLING, MAINTAINING, REMOVING, OR REPLACING ANY PORTION OF UNDERGROUND WATER, SANITARY SEWER OR STORM SEWER FACILITIES.

5. THE FOREGOING COVENANTS SET FORTH IN THIS PARAGRAPH SHALL BE ENFORCEABLE BY THE CITY OF JENKS, OKLAHOMA, OR ITS SUCCESSORS, AND THE OWNER OF THE LOT AGREES TO BE BOUND HEREBY.

D. SURFACE DRAINAGE

EACH LOT DEPICTED ON THE PLAT OF YORKTOWN BLOCKS 39-44, SHALL RECEIVE AND DRAIN, IN AN UNOBSTRUCTED MANNER, THE STORM AND SURFACE WATERS FROM LOTS AND DRAINAGE AREAS OF HIGHER ELEVATION AND FROM STREETS AND EASEMENTS. NO LOT OWNER(S), SHALL CONSTRUCT OR PERMIT TO BE CONSTRUCTED ANY FENCING OR OTHER OBSTRUCTIONS WHICH WOULD IMPAIR THE DRAINAGE OF STORM AND SURFACE WATERS OVER AND ACROSS ANY LOT. THE FOREGOING COVENANTS SET FORTH IN THIS PARAGRAPH SHALL BE ENFORCEABLE BY ANY AFFECTED LOT OWN R AND BY THE CITY OF JENKS, OKLAHOMA.

E. PAVING AND LANDSCAPING WITHIN EASEMENT

THE OWNER OF THE LOT AFFECTED SHALL BE RESPONSIBLE FOR THE REPAIR OF DAMAGE TO LANDSCAPING AND PAVING OCCASIONED BY NECESSARY PLACEMENTS, REPLACEMENTS, OR MAINTENANCE OF WATER, SEWER, STORM SEWER, NATURAL GAS, COMMUNICATION, CABLE TELEVISION, OR ELECTRIC FACILITIES WITHIN THE UTILITY EASEMENT AREAS DEPICTED UPON THE ACCOMPANYING PLAT, PROVIDED HOWEVER, THE CITY OF JENKS, OKLAHOMA OR THE SUPPLIER OF THE UTILITY SERVICE SHALL USE REASONABLE CARE IN THE PERFORMANCE OF SUCH ACTIVITIES.

F. LIMITS OF NO ACCESS

THE UNDERSIGNED OWNER HEREBY RELINQUISHES RIGHTS OF VEHICULAR INGRESS OR EGRESS FROM ANY PORTION OF THE PROPERTY ADJACENT TO EAST 131ST STREET SOUTH WITHIN THE BOUNDS DESIGNATED AS "LIMITS OF NO ACCESS" ON THE ACCOMPANYING PLAT, WHICH "LIMITS OF NO ACCESS" MAY BE AMENDED OR RELEASED BY THE CITY OF JENKS, OKLAHOMA, OR ITS SUCCESSOR, OR AS OTHERWISE PROVIDED BY THE STATUTES AND LAWS OF THE STATE OF OKLAHOMA. "LIMITS OF NO ACCESS" SHALL BE ENFORCEABLE BY THE CITY OF JENKS.

G. OVERLAND DRAINAGE EASEMENTS

1. OVERLAND DRAINAGE EASEMENTS DESIGNATED ON THE PLAT ARE HEREBY DEDICATED TO THE CITY OF JENKS OR ITS SUCCESSORS FOR THE PURPOSE OF MAINTAINING, CONSTRUCTING OR REPAIRING ALL DRAINAGE FACILITIES WITHIN THESE EASEMENTS MAY BE USED FOR UTILITIES ACCORDING TO THE PROVISIONS IN THE CERTIFICATE OF DEDICATION AS IT APPLIES TO EASEMENTS, EXCEPT THAT CONSTRUCTION AND USE OF UTILITIES THEREIN SHALL NOT INTERFERE WITH THE USE FOR DRAINAGE PURPOSES.

2. NO BUILDING STRUCTURE, WALL, FENCE, OR ABOVE OR BELOW GROUND OBSTRUCTIONS SHALL BE CONSTRUCTED OR PLACED WITHIN ANY DRAINAGE EASEMENT WITHOUT APPROVAL OF THE CITY OF JENKS.

3. THE OWNER OF EACH LOT UPON WHICH A DRAINAGE EASEMENT IS SITUATED SHALL BE SOLELY RESPONSIBLE FOR THE MAINTENANCE OF ANY SAID EASEMENT WHICH TRAVERSES THEIR RESPECTIVE PROPERTY.

4. IN THE EVENT OWNER SHOULD FAIL TO PROPERLY MAINTAIN THE DRAINAGE FACILITIES OR, IN THE EVENT OF THE PLACEMENT OF AN OBSTRUCTION WITHIN, OR THE ALTERATION OF THE CONTOUR THEREIN, THE CITY OF JENKS OR ITS DESIGNATED CONTRACTOR MAY ENTER AND PERFORM MAINTENANCE NEC'Y TO THE ACHIEVEMENT OF THE INTENDED DRAINAGE FUNCTIONS AND MAY REMOVE ANY OBSTRUCTION OR CORRECT BY THE OWNER, OR THE HOMEOWNER'S ASSOCIATION. IN THE COST THEREOF SHALL BE PAID BY THE OWNER, OR THE HOMEOWNER'S ASSOCIATION. III. THE EVENT OWNER OR THE HOMEOWNER'S ASSOCIATION, AS THE CASE MAY BE, FAILS TO PAY THE COST OF MAINTENANCE AFTER COMPLETION OF THE MAINTENANCE AND RECEIPT OF A STATEMENT OF COSTS, THE CITY OF JENKS, MAY FILE OF RECORD A COPY OF THE STATEMENT OF COSTS, AND THEREAFTER FILE A LIEN AGAINST THE SUBJECT LOT, SUCH LIEN, HOWEVER, SHALL BE SUBORDINATE TO THE LIEN OF ANY FIRST MORTGAGE. A LIEN ESTABLISHED AS ABOVE PROVIDED MAY BE FORECLOSED BY THE CITY OF JENKS.

G. STORM WATER DETENTION

1. THE OWNER/DEVELOPER DOES HEREBY GRANT AND ESTABLISH A PERPETUAL EASEMENT ON, OVER AND ACROSS RESERVE AREA 'A' (HEREINAFTER REFERRED TO AS THE "DETENTION EASEMENT AREA") FOR THE PURPOSES OF PERMITTING THE FLOW, CONVEYANCE, DETENTION AND DISCHARGE OF STORM WATER RUNOFF FROM THE VARIOUS LOTS WITHIN THE SUBDIVISION.

2. DETENTION AND OTHER DRAINAGE FACILITIES CONSTRUCTED WITHIN THE DETENTION EASEMENT AREAS SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS APPROVED BY THE CITY OF JENKS, OKLAHOMA.

3. DETENTION AND OTHER DRAINAGE FACIL IES SHALL BE MAINTAINED BY THE HOMEOWNERS' ASSOCIATION (TO BE FORMED PURSUANT TO SECTION IV) TO THE EXTENT NECESSARY TO ACHIEVE THE INTENDED DRAINAGE AND DETENTION FUNCTIONS INCLUDING REPAIR OF APPURTENANCES AND REMOVAL OF OBSTRUCTIONS AND SILTATION. THE HOMEOWNERS' ASSOCIATION SHALL PROVIDE ROUTINE AND CUSTOMARY GROUNDS MAINTENANCE WITHIN THE DETENTION EASEMENT AREAS WHICH SHALL BE IN ACCORDANCE WITH THE FOLLOWING STANDARDS:

THE DETENTION EASEMENT AREAS SHALL BE KEPT FREE OF LITTER.

THE DETENTION EASEMENT AREAS SHALL BE MOWED DURING THE GROWING SEASON AT INTERVALS NOT EXCEEDING 4 WEEKS.

4. IN THE EVENT THE HOMEOWNERS' ASSOCIATION SHOULD FAIL TO PROPERLY MAINTAIN THE DETENTION EASEMENT AREAS AS ABOVE PROVIDED, THE CITY OF JENKS, OKLAHOMA, OR ITS DESIGNATED CONTRACTOR MAY ENTER THE DETENTION EASEMENT AREAS AND PERFORM SUCH MAINTENANCE, AND THE COST THEREOF SHALL BE PAID BY THE HOMEOWNERS' ASSOCIATION.

5. IN THE EVENT THE HOMEOWNERS' ASSOCIATION, AFTER COMPLETION OF THE MAINTENANCE AND RECEIPT OF A STATEMENT OF COSTS, FAILS TO PAY THE COST OF MAINTENANCE AS ABOVE SET FORTH, THE CITY OF JENKS, OKLAHOMA MAY FILE OF RECORD A COPY OF THE STATEMENT OF COSTS AND THEREAFTER THE COSTS SHALL BE A LIEN AGAINST EACH RESIDENTIAL LOT WITHIN THE SUBDIVISION, PROVIDED HOWEVER, THE LIEN AGAINST EACH RESIDENTIAL LOT SHALL BE LIMITED TO ITS PROPORTIONATE SHARE OF THE COSTS.

6. A LIEN ESTABLISHED AS ABOVE PROVIDED MAY BE FORECLOSED BY THE CITY OF JENKS, OKLAHOMA.

H. RESERVE AREA "A" & U/E

RESERVE AREA "A" & U/E IS HEREBY DEDICATED FOR THE PURPOSE OF ESTABLISHING AND MAINTAINING DETENTION FACILITIES, UTILITY EASEMENT, OPEN SPACE, RECREATION, LANDSCAPING, SCREENING FENCES AND WALLS, AND IS RESERVED FOR SUBSEQUENT CONVEYANCE TO THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION, FOR THEIR USE AND MAINTENANCE, TO BE COMPRISED OF THE OWNERS OF ALL RESIDENTIAL LOTS WITHIN THE YORKTOWN DEVELOPMENT COMMUNITY AS SET FORTH WITHIN SECTION IV HEREOF.

I. RESERVE AREA "B" & U/E

RESERVE AREA "B" & U/E IS HEREBY DEDICATED FOR THE PURPOSE OF ESTABLISHING AND MAINTAINING OVERLAND DRAINAGE EASEMENT, UTILITY EASEMENT, OPEN SPACE, LANDSCAPING, SCREENING FENCES AND WALLS, AND IS RESERVED FOR SUBSEQUENT CONVEYANCE TO THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION, FOR THEIR USE AND MAINTENANCE, TO BE COMPRISED OF THE OWNERS OF ALL RESIDENTIAL LOTS WITHIN THE YORKTOWN DEVELOPMENT COMMUNITY AS SET FORTH WITHIN SECTION IV HEREOF.

J. RESERVE AREAS "C" & U/E AND "D" & U/E

RESERVE AREAS "C" & U/E AND "D" & U/E SHALL BE LIMITED TO USE FOR LANDSCAPING, UTILITIES AND OPEN SPACE AND ARE RESERVED FOR SUBSEQUENT CONVEYANCE TO THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION, FOR THEIR USE AND MAINTENANCE, TO BE COMPRISED OF THE OWNERS OF ALL RESIDENTIAL LOTS WITHIN THE YORKTOWN DEVELOPMENT COMMUNITY AS SET FORTH WITHIN SECTION IV HEREOF.

SECTION II. PLANNED UNIT DEVELOPMENT RESTRICTIONS

WHEREAS, "YORKTOWN BLOCKS 39-44" WAS SUBMITTED AS PART OF A PLANNED UNIT DEVELOPMENT MAJOR AMENDMENT (DESIGNATED AS PUD 61 AMENDED "C"), AS PROVIDED WITHIN SECTIONS 900 THROUGH 950 OF THE CITY OF JENKS ZONING CODE, AS THE SAME EXISTED ON MARCH 23, 2012, (HEREINAFTER THE "JENKS ZONING CODE"), AND

WHEREAS PUD 61 AMENDED "C" WAS AFFIRMATIVELY RECOMMENDED BY THE JENKS PLANNING COMMISSION AND APPROVED BY THE JENKS CITY COUNCIL, AND

WHEREAS, THE PLANNED UNIT DEVELOPMENT PROVISIONS OF THE JENKS ZONING CODE REQUIRE THE ESTABLISHMENT OF COVENANTS OF RECORD, INURING TO AND ENFORCEABLE BY THE CITY OF JENKS, OKLAHOMA, SUFFICIENT TO ASSURE THE IMPLEMENTATION AND CONTINUED COMPLIANCE WITH THE APPROVED PLANNED UNIT DEVELOPMENT AND AMENDMENTS THERETO, AND

WHEREAS, THE OWNERS ESTABLISHED RESTRICTIONS FOR THE PURPOSE OF PROVIDING FOR AN ORDERLY DEVELOPMENT AND TO INSURE ADEQUATE RESTRICTIONS FOR THE MUTUAL BENEFIT OF THE OWNER, ITS SUCCESSORS AND ASSIGNS, AND THE CITY OF JENKS, OKLAHOMA, AND

THEREFORE, THE OWNERS DO HEREBY IMPOSE RESTRICTIONS AND COVENANTS TO ALL LOTS CONTAINED WITHIN THIS SUBDIVISION PLAT (YORKTOWN BLOCKS 39-44), AND WHICH COVENANTS SHALL BE COVENANTS RUNNING WITH THE LAND AND SHALL BE BINDING UPON THE OWNER, ITS SUCCESSORS AND ASSIGNS, AND SHALL BE ENFORCEABLE AS HEREINAFTER SET FORTH.

GROSS LAND AREA: 34.728 ACRES (1,512,772.72 SF)
EXISTING ZONING: PUD 61 AMENDED "C" / RS-2

YORKTOWN BLOCKS 39-44 NEIGHBORHOOD P.U.D. DEVELOPMENT STANDARDS INCLUDES ALL LOTS LOCATED WITHIN YORKTOWN BLOCKS 39-44:

PERMITTED USES:

USE UNIT 6, SINGLE-FAMILY DWELLINGS, AND CUSTOMARY FACILITIES AND AMENITIES, INCLUSIVE OF COMMON SPACE AREA USES AND ACTIVITIES GENERALLY FOUND WITHIN MASTER-PLANNED RESIDENTIAL COMMUNITIES.

MINIMUM LOT WIDTH: 60 FEET

MINIMUM LOT AREA: 7,200 SQUARE FEET

MINIMUM DWELLING SIZE: MINIMUM OF 1,500 SQUARE FEET OF FINISHED HEATED LIVING AREA.

MINIMUM BUILDING SETBACKS:

FROM INTERNAL STREET RIGHT-OF-WAY LIMITS: 25 FEET, WITH THE EXCEPTION OF CORNER SUBDIVISION LOTS WHICH MAY HAVE ONE 15' B/L SETBACK ALONGSIDE ONE STREET IN WHICH THE LOT HAS FRONTAGE UPON. IN THOSE PARTICULAR INSTANCES IN WHICH THE FRONT FACE OF A HOME ON A CORNER LOT IS DIRECTED TOWARDS THE 15' B/L SETBACK OF THE CORNER LOT, A MINIMUM 25' B/L SETBACK MUST BE MAINTAINED FROM THE OTHER STREET FRONTAGE RIGHT-OF-WAY ABUTTING THAT CORNER LOT. ADDITIONALLY, ON ALL CORNER SUBDIVISION LOTS IN WHICH THE FRONT FACE OF THE HOME IS DIRECTED TOWARDS THE 25' B/L SETBACK AND A SIDE-LOADED GARAGE IS PROPOSED (GARAGE DOORS FACING TOWARDS THE 15' B/L SETBACK), A MINIMUM 20' B/L SETBACK FROM THE STREET RIGHT-OF-WAY MUST BE MAINTAINED FOR SUCH SIDE-LOADED GARAGES.

FROM ULTIMATE RIGHT-OF-WAY LIMITS OF ALL ARTERIAL STREETS (E. 131ST STREET S.): 35 FEET

FROM SIDE LOT LINES: 5 FEET

FROM REAR LOT LINES: 25 FEET

MAXIMUM STRUCTURE HEIGHT:

35 FEET, WITH THE EXCEPTION OF CHIMNEYS, CUPOLAS, OR OTHER ARCHITECTURAL STRUCTURES WHICH MAY EXTEND TO A MAXIMUM HEIGHT OF 45'.

SECTION III. PRIVATE BUILDING AND USE RESTRICTIONS

WHEREAS, THE OWNERS DESIRE TO ESTABLISH ADDITIONAL RESTRICTIONS FOR "YORKTOWN BLOCKS 39-44" FOR THE PURPOSE OF PROVIDING AN ORDERLY DEVELOPMENT OF THE RESIDENTIAL NEIGHBORHOODS WITHIN YORKTOWN BLOCKS 39-44, AND TO ENSURE ADEQUATE RESTRICTIONS FOR THE MUTUAL BENEFIT OF THE OWNERS, ITS SUCCESSORS AND ASSIGNS.

THEREFORE, THE OWNERS DO HEREBY AND LIKEWISE IMPOSE THE FOLLOWING RESTRICTIONS AND COVENANTS UPON THE LOTS WITHIN THIS SUBDIVISION PLAT (YORKTOWN BLOCKS 39-44) WHICH SHALL BE COVENANTS RUNNING WITH THE LAND, AND SHALL BE BINDING UPON THE OWNERS, THEIR SUCCESSORS AND ASSIGNS:

A. ARCHITECTURAL COMMITTEE - PLAN REVIEW

1. NO BUILDING, FENCE, WALL OR LANDSCAPING SHALL BE ERECTED, PLACED OR ALTERED ON ANY RESIDENTIAL LOT IN THIS SUBDIVISION UNTIL THE BUILDING PLANS, LANDSCAPING PLANS, AND SPECIFICATIONS FOR ALL HOUSES TO BE BUILT, AND LANDSCAPING TO BE INSTALLED, ARE ON FILE WITH THE YORKTOWN ARCHITECTURAL COMMITTEE. INITIALLY TO BE YORKTOWN HOLDING, LLC MEMBERS OR THEIR DULY AUTHORIZED REPRESENTATIVE, REPRESENTATIVES OR SUCCESSORS. IN THE EVENT OF THE DEATH OR RESIGNATION OF ANY MEMBER OF THE YORKTOWN ARCHITECTURAL COMMITTEE, THE REMAINING MEMBER OR MEMBERS SHALL HAVE FULL AUTHORITY TO APPROVE OR DISAPPROVE SUCH PLANS, SPECIFICATIONS, COLOR SCHEME, MATERIALS AND PLOT PLAN, OR TO DESIGNATE A REPRESENTATIVE OR REPRESENTATIVES WITH THE LIKE AUTHORITY, AND SAID REMAINING MEMBER OR MEMBERS SHALL HAVE AUTHORITY TO FILL ANY VACANCY OR VACANCIES CREATED BY THE DEATH OR RESIGNATION OF ANY OF THE AFORESAID MEMBERS, AND SAID NEWLY APPOINTED MEMBER SHALL HAVE THE SAME AUTHORITY HEREUNDER AS THEIR PREDECESSORS, AS ABOVE SET FORTH. ANY CHANGES TO PLANS ON FILE WITH THE ARCHITECTURAL COMMITTEE OR ANY ADDITIONAL NEW PLANS WILL NEED WRITTEN APPROVAL BEFORE CONSTRUCTION MAY BEGIN.

2. THE ARCHITECTURAL COMMITTEE'S PURPOSE IS TO PROMOTE GOOD DESIGN AND COMPATIBILITY WITHIN THE SUBDIVISION AND IN ITS REVIEW OF BUILDING OR LANDSCAPING PLANS FOR DETERMINATION OF ANY WAIVER AS HEREINAFTER AUTHORIZED MAY TAKE INTO CONSIDERATION THE NATURE AND CHARACTER OF THE PROPOSED BUILDING OR STRUCTURE, THE MATERIALS OF WHICH IT IS TO BE BUILT, THE AVAILABILITY OF ALTERNATIVE MATERIALS, THE SITE UPON WHICH IT IS PROPOSED TO BE ERECTED AND THE HARMONY THEREOF WITH THE SURROUNDING AREA. THE ARCHITECTURAL COMMITTEE SHALL NOT BE LIABLE FOR ANY APPROVAL, DISAPPROVAL OR FAILURE TO APPROVE HEREUNDER, AND ITS APPROVAL OF BUILDING PLANS SHALL NOT CONSTITUTE A WARRANTY OR RESPONSIBILITY FOR BUILDING METHODS, MATERIALS, PROCEDURES, STRUCTURAL DESIGN, GRADING OR DRAINAGE, OR CODE VIOLATIONS. THE APPROVAL, DISAPPROVAL OR FAILURE TO APPROVE OF ANY BUILDING PLANS SHALL NOT BE DEEMED A WAIVER OF ANY RESTRICTION, UNLESS THE ARCHITECTURAL COMMITTEE IS HEREINAFTER AUTHORIZED TO GRANT THE PARTICULAR WAIVER.

3. THE POWERS AND DUTIES OF THE ARCHITECTURAL COMMITTEE OR ITS DESIGNATED REPRESENTATIVE SHALL CEASE WHEN ONE-HUNDRED PERCENT (100%) OF THE HOUSES ON THE RESIDENTIAL LOTS HAVE BEEN BUILT. THEREAFTER, THE POWERS AND DUTIES OF THE ARCHITECTURAL COMMITTEE SHALL BE EXERCISED BY THE HOMEOWNERS ASSOCIATION HEREAFTER PROVIDED FOR.

B. BUILDING MATERIAL REQUIREMENTS AND OTHER RESTRICTIONS APPLICABLE TO ALL RESIDENTIAL LOTS CONTAINED WITHIN YORKTOWN BLOCKS 39-44

1. STEM WALLS:

ALL EXPOSED FOUNDATION OR STEM WALLS SHALL BE OF BRICK, STONE OR STUCCO. NO CONCRETE BLOCKS, POURED CONCRETE OR ANY OTHER FOUNDATION WILL BE EXPOSED. NO STEM WALLS WILL BE EXPOSED.

2. ROOFING:

ROOFING SHALL BE A SINGULAR ROOF SELECTION AND COLOR FOR EACH RESPECTIVE NEIGHBORHOOD COMMUNITY WITHIN YORKTOWN, AND THE OWNER/DEVELOPER SHALL HAVE THE RIGHT TO SELECT A DIFFERENT ROOFING COLOR FOR EACH NEIGHBORHOOD COMMUNITY WITHIN YORKTOWN. THE MINIMUM ROOF PITCH SHALL BE AN 8/12 PITCH ON THE FORWARD FACING GABLES.

3. EXTERIOR WALLS:

THE FIRST STORY EXTERIOR WALLS OF THE DWELLINGS ERECTED ON ALL RESIDENTIAL LOTS WITHIN THE YORKTOWN BLOCKS 39-44 NEIGHBORHOOD SHALL BE ONE-HUNDRED PERCENT (100%) BRICK, STONE, OR STUCCO, PROVIDED, HOWEVER, THAT THE AREA OF ALL WINDOWS AND DOORS LOCATED IN SAID EXTERIOR WALLS AND THE AREA ADJACENT TO PATIOS AND UNDER PORCHES SHALL BE EXCLUDED IN THE DETERMINATION OF THE AREA OF EXTERIOR WALLS, AND FURTHER PROVIDED THAT WHERE A PART OF THE EXTERIOR WALL IS EXTENDED ABOVE THE INTERIOR ROOM CEILING LINE DUE TO THE CONSTRUCTION OF A GABLE TYPE ROOF, THEN THAT PORTION OF THE WALL EXTENDING ABOVE THE INTERIOR ROOM CEILING HEIGHT MAY BE CONSTRUCTED OF WOOD MATERIAL AND SHALL BE EXCLUDED FROM THE DETERMINATION OF THE AREA OF THE EXTERIOR WALLS (EXCLUSIVE OF FIREPLACE CHASE).

4. MINIMUM SQUARE FOOTAGE:

AS DESCRIBED ABOVE UNDER SECTION II. PLANNED UNIT DEVELOPMENT RESTRICTIONS.

5. MINIMUM LOT WIDTH:

AS DESCRIBED ABOVE UNDER SECTION II. PLANNED UNIT DEVELOPMENT RESTRICTIONS.

6. MINIMUM LOT AREA:

AS DESCRIBED ABOVE UNDER SECTION II. PLANNED UNIT DEVELOPMENT RESTRICTIONS.

7. WINDOWS:

ALL DWELLINGS WITH WINDOWS OTHER THAN WOOD OR VINYL WILL BE EITHER ANODIZED OR ELECTROSTATICALLY PAINTED. METAL WINDOW FRAMES SHALL BE CONSISTENT WITH THE EXTERIOR COLOR AND TEXTURE OF THE RESIDENCE. NO UNPAINTED ALUMINUM WILL BE PERMITTED FOR WINDOW FRAMING. WOOD FRAMES WILL BE PAINTED, SEALED OR STAINED.

8. SIDING:

NO STEEL, ALUMINUM OR PLASTIC SIDING SHALL BE PERMITTED ON ANY BUILDING ON ANY RESIDENTIAL LOT.

9. MAILBOXES:

ALL MAILBOXES SHALL BE OF A SINGULAR DESIGN FOR THE LOTS WITHIN YORKTOWN BLOCKS 39-44, AS APPROVED BY THE ARCHITECTURAL COMMITTEE. NO MAILBOX SHALL BE ERECTED ON ANY RESIDENTIAL LOT WITHOUT THE APPROVAL OF THE DESIGN BY THE ARCHITECTURAL COMMITTEE, AND SHALL CONFORM TO A DESIGN STANDARD FOR EACH COMMUNITY. A CHARGE FOR MAILBOXES WILL BE COLLECTED BY THE OWNER/DEVELOPER AT THE CLOSING OF EACH LOT.

10. WAIVER:

THE ARCHITECTURAL COMMITTEE MAY WAIVE, IN A PARTICULAR INSTANCE, THE BUILDING MATERIAL REQUIREMENTS SET OUT IN THIS SUBSECTION; PROVIDED, SUCH WAIVER TO BE EFFECTIVE MUST BE IN WRITING, DATED AND SIGNED BY A MAJORITY OF THE ARCHITECTURAL COMMITTEE.

A. NOXIOUS ACTIVITY

NO NOXIOUS OR OFFENSIVE TRADE OR ACTIVITY SHALL BE CARRIED ON UPON ANY RESIDENTIAL LOT WITHIN THIS SUBDIVISION, NOR SHALL ANY TRASH, OR OTHER REFUSE BE THROWN, PLACED OR DUMPED UPON ANY VACANT RESIDENTIAL LOT, NOR SHALL ANYTHING BE DONE WHICH MAY BE OR BECOME AN ANNOYANCE OR NUISANCE TO THE NEIGHBORHOOD.

B. EXISTING BUILDING

NO EXISTING OR ERECTED BUILDING OF ANY SORT MAY BE MOVED ONTO OR PLACED ON AN RESIDENTIAL LOT, EXCEPT FOR CONSTRUCTION OR SALES TRAILERS WHICH MAY BE INSTALLED ON A TEMPORARY BASIS ONLY.

C. DETACHED STRUCTURES PROHIBITION

NO DETACHED ACCESSORY STRUCTURE SHALL BE ALLOWED UPON ANY LOT WITHIN THE YORKTOWN DEVELOPMENT.

D. VEHICLE STORAGE AND PARKING

NO INOPERATIVE VEHICLE SHALL BE STORED ON ANY RESIDENTIAL LOT EXCEPT WITHIN AN ENCLOSED GARAGE. NO MOTOR HOME, BOAT TRAILER, TRAVEL TRAILER OR SIMILAR RECREATIONAL VEHICLE SHALL BE LOCATED, PARKED OR STORED WITHIN A SIDE OR FRONT YARD, AND IF NOT LOCATED WITHIN AN ENCLOSED GARAGE AND SHALL BE SCREENED SUFFICIENTLY TO PREVENT ANY VIEW THEREOF FROM ANY STREET WITHIN THE OVERALL YORKTOWN DEVELOPMENT.

E. ANTENNAS

NO RADIO OR TELEVISION TOWER, AERIAL OR ANTENNA SHALL BE LOCATED ON ANY RESIDENTIAL LOT. SATELLITE DISHES SHALL BE NO LARGER THAN 18" IN DIAMETER AND BE SCREENED FROM VIEW FROM THE STREET AND ADJACENT RESIDENTIAL LOTS WITHIN THE ADDITION.

F. LANDSCAPING REQUIREMENTS

THE FRONT ELEVATION OF ALL RESIDENTIAL LOTS MUST BE PROFESSIONALLY LANDSCAPED UPON COMPLETION OF THE RESIDENCE. ALL FRONT, SIDE AND BACK YARDS MUST BE SODDED ON THE COMPLETION OF ANY RESIDENCE IN THE SUBDIVISION. ALL PROPOSED LANDSCAPING UPON EVERY LOT WITHIN THIS SUBDIVISION MUST RECEIVE APPROVAL BY THE ARCHITECTURAL COMMITTEE AS DESCRIBED UNDER SECTION III.A HEREOF.

G. LIVESTOCK AND POULTRY PROHIBITED

NO ANIMALS, LIVESTOCK OR POULTRY (INCLUDING PIGEONS) OF ANY KIND SHALL BE RAISED, BRED OR KEPT ON ANY RESIDENTIAL LOT OR PART THEREOF, EXCEPT THAT DOGS, CATS, OR OTHER HOUSEHOLD PETS MAY BE KEPT; PROVIDED, THAT THEY ARE NOT KEPT, BRED OR MAINTAINED FOR ANY COMMERCIAL PURPOSE.

H. FENCES AND WALLS

FENCES AND WALLS SITUATED UPON RESIDENTIAL LOTS SHALL COMPLY WITH THE FOLLOWING:

1. NO FENCING SHALL EXTEND BEYOND THE BUILDING LINE OF ANY RESIDENCE. IF A RESIDENCE IS BUILT BEHIND THE FRONT BUILDING LINE OF A RESIDENTIAL LOT, A FENCE MAY NOT EXTEND BEYOND THAT POINT NEAREST THE STREET AT EACH END CORNER.

2. ALL FENCES SHALL CONSIST ENTIRELY OF WOOD, BRICK, NATURAL STONE, WROUGHT IRON, OR SOME COMBINATION THEREOF. THE ARCHITECTURAL COMMITTEE MAY, BUT NOT BE OBLIGATED TO, GRANT AN EXCEPTION TO THIS PROVISION UPON WRITTEN REQUEST. NO CHAIN LINK, BARBED WIRE, MESH OR OTHER METAL FENCING SHALL BE PERMITTED UNDER ANY CIRCUMSTANCES, WITH THE EXCEPTION OF A POSSIBLE VINYL-COATED OR ACID-STAINED FENCE WITHIN THE LINEAR RESERVE AREAS ALONGSIDE THE REAR LOT LINES OF THOSE SUBDIVISION LOTS THAT ABOUT THE PERIMETER OF THE YORKTOWN PROJECT.

3. NO FENCE IN EXCESS OF SIX FEET (6') IN HEIGHT SHALL BE PERMITTED UNLESS OTHERWISE APPROVED BY THE ARCHITECTURAL COMMITTEE IN WRITING.

4. ALL FENCING ADJACENT TO RESERVE 'A' MUST BE CONSISTENT. ANY VARIANCE MUST BE APPROVED BY THE ARCHITECTURAL COMMITTEE.

K. GARAGE

EACH DWELLING SHALL HAVE A GARAGE FOR AT LEAST TWO AUTOMOBILES. GLASS SHALL NOT BE PERMITTED IN GARAGE DOORS WITHOUT ARCHITECTURAL COMMITTEE APPROVAL.

L. COMMERCIAL STRUCTURES

NO BUILDING OR STRUCTURE SHALL BE PLACED, ERECTED OR USED AT ANY TIME FOR ANY BUSINESS, PROFESSIONAL, TRADE OR COMMERCIAL PURPOSE ON ANY PORTION OF ANY RESIDENTIAL LOT; PROVIDED, HOWEVER, THAT OWNER, AS THE DEVELOPER OF THE SUBDIVISION MAY MAINTAIN A SALES OFFICE IN THE SUBDIVISION FOR THE SALE OF THE SUBDIVISION LOTS AND BUILDING CONTRACTORS MAY MAINTAIN SALES OFFICES, CONSTRUCTION TRAILERS, AND MODEL HOMES IN THE SUBDIVISION FOR THE CONSTRUCTION, SALE AND DISPLAY OF HOMES LOCATED, OR TO BE LOCATED, IN THE SUBDIVISION SUBJECT TO THE CITY OF JENKS ZONING CODE REQUIREMENTS.

M. TRASH RECEPTACLES

TRASH RECEPTACLES CANNOT BE LEFT CURBSIDE FOR MORE THAN A 24 HOUR PERIOD OF TIME. ALL TRASH RECEPTACLES SHALL BE KEPT INSIDE OF A GARAGE OR SCREENED FROM VIEW FROM ALL STREETS WITHIN THE SUBDIVISION.

N. BUILDING REQUIREMENTS AND AMENDMENTS

ANY MODIFICATIONS OR AMENDMENTS TO THE BUILDING AND/OR ARCHITECTURAL REQUIREMENTS LISTED UNDER THIS SECTION (SECTION III. PRIVATE BUILDING AND USE RESTRICTIONS) SHALL ONLY BE ALLOWED WITH ARCHITECTURAL COMMITTEE APPROVAL AS DESCRIBED UNDER SECTION III.A HEREOF.

SECTION IV. HOMEOWNERS ASSOCIATION

A. FORMATION OF MASTER AND NEIGHBORHOOD HOMEOWNERS ASSOCIATIONS

THE OWNERS OF YORKTOWN BLOCKS 39-44 FORMED A MASTER HOMEOWNERS ASSOCIATION (YORKTOWN MASTER HOMEOWNERS ASSOCIATION) WHICH IS THE PRINCIPLE HOMEOWNERS ASSOCIATION AFFECTING AND INCLUDING EACH OWNER OF A LOT OF RECORD WITHIN ALL OF THE CURRENT AND FUTURE YORKTOWN NEIGHBORHOOD COMMUNITIES, OF WHICH SAID COMMUNITIES AND FUTURE DEVELOPMENT AREAS CONTAIN APPROXIMATELY 225 ACRES OF LAND AND ARE AS SHOWN WITHIN THE APPROVED YORKTOWN PLANNED UNIT DEVELOPMENT (PUD NO. 61). ADDITIONALLY, ALL OF THE CURRENT AND FUTURE YORKTOWN NEIGHBORHOOD COMMUNITIES SHALL ALSO BE MEMBERS OF A YORKTOWN NEIGHBORHOOD HOMEOWNERS ASSOCIATION CONSISTING OF DEFINED LOTS AND BLOCKS REPRESENTING THE INDIVIDUAL NEIGHBORHOODS WITHIN THE OVERALL YORKTOWN DEVELOPMENT COMMUNITY. THE YORKTOWN MASTER AND NEIGHBORHOOD HOMEOWNERS ASSOCIATIONS HAVE / SHALL BE ESTABLISHED IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OKLAHOMA, AND ARE TO BE FORMED FOR THE GENERAL PURPOSES OF MAINTAINING THE COMMON AREAS OF THE OVERALL YORKTOWN COMMUNITY, AND ENHANCING THE VALUE, DESIRABILITY AND ATTRACTIVENESS OF THE YORKTOWN COMMUNITY.

B. MEMBERSHIP

ANY OWNER OF A LOT IN THE OVERALL YORKTOWN COMMUNITY SHALL AUTOMATICALLY BECOME A MEMBER OF THE NEIGHBORHOOD HOMEOWNERS ASSOCIATION FOR THAT RESPECTIVE NEIGHBORHOOD COMMUNITY IN WHICH SUCH LOT BELONGS. EACH NEIGHBORHOOD COMMUNITY SHALL LIKEWISE AUTOMATICALLY BECOME MEMBERS OF THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION (YMHA). MEMBERSHIP OF THE NEIGHBORHOOD HOMEOWNERS ASSOCIATION SHALL BE LIMITED TO THE RECORD OWNER, WHETHER ONE OR MORE PERSONS OR ENTITIES, OF A FEE SIMPLE TITLE TO A LOT SITUATED WITHIN ALL OF THE CURRENT AND FUTURE YORKTOWN NEIGHBORHOODS COMPRISING THE OVERALL YORKTOWN COMMUNITY. IN ADDITION, OWNERS OF LOTS OF RECORD WITHIN THE PRESENTLY PLATTED AND DEVELOPED NEIGHBORHOOD COMMUNITY OF "WESTON AT WAKEFIELD" AND "WESTON II AT WAKEFIELD" SHALL BE ALLOWED TO PARTICIPATE IN THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION AND HAVE PRIVILEGES AND RIGHTS TO THE FULL USE AND ENJOYMENT OF THE COMMUNITY POOL AND IMPROVEMENTS LOCATED WITHIN RESERVE AREA "G" OF YORKTOWN PHASE I, AND OTHER CERTAIN YORKTOWN COMMUNITY COMMON AREAS AS TO BE SET FORTH BY THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION. SUCH LOT OWNERS SHALL BE ENTITLED TO THESE PRIVILEGES ON AN INDIVIDUAL BASIS, YEARLY, BY PAYING THE ANNUAL YMHA DUES (EQUAL TO AMOUNT PAID BY YORKTOWN RESIDENTS). THE FOREGOING IS NOT INTENDED TO INCLUDE PERSONS OR ENTITIES THAT HOLD AN INTEREST MERELY AS SECURITY FOR THE PERFORMANCE OF AN OBLIGATION, OTHER THAN CONTRACT SELLERS. MEMBERSHIP SHALL BE APPURTENANT TO AND MAY NOT BE SEPARATED FROM OWNERSHIP OF ANY LOT SITUATED WITHIN THE YORKTOWN COMMUNITY OR SUCH NEIGHBORHOOD COMMUNITIES THAT MAY BE ANNEXED OR MERGED INTO THE JURISDICTION OF THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION. OWNERSHIP OF A LOT SHALL BE THE SOLE QUALIFICATION OF MEMBERSHIP WITH RESPECT TO THOSE PROPERTY OWNERS IN YORKTOWN.

C. ASSESSMENT

EACH RECORD OWNER OF A RESIDENTIAL LOT WITHIN THE OVERALL YORKTOWN COMMUNITY SHALL BE SUBJECT TO ASSESSMENT BY THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION THROUGH THEIR COMMUNITY MEMBERSHIP FOR THE PURPOSES OF IMPROVEMENT AND MAINTENANCE OF THE PRIMARY COMMON AREAS OF THE YORKTOWN PHASE I SUBDIVISION, WHICH CONSIST OF RESERVE AREAS "A", "B", "C" & U/E, "F" & U/E, "G", "H" & U/E, "I" & U/E, "L" & U/E, "M" & U/E, "O", "P" & U/E, AND "Q" & U/E OF YORKTOWN PHASE I; RESERVE AREAS "A" & U/E AND "B" & U/E, HENLEY AT YORKTOWN; RESERVE AREA "D" & U/E, BIRMINGHAM AT YORKTOWN; RESERVE AREAS "E" & U/E, "F" & U/E, AND "G" & U/E, MANCHESTER AT YORKTOWN; RESERVE AREA "H", BIRMINGHAM AT YORKTOWN, BLOCKS 24-30; RESERVE AREA "A", YORKTOWN, BLOCKS 31-35; RESERVE AREAS "A" & U/E, "B" & U/E, "C" & U/E AND "D" & U/E, SHELBY AT YORKTOWN, BLOCKS 36-38; RESERVE AREAS "A" & U/E AND "B" & U/E, AND YORKTOWN BLOCKS 39-44; RESERVE AREAS "A" & U/E, "B" & U/E, "C" & U/E AND "D" & U/E. EACH RECORD OWNER OF A RESIDENTIAL LOT WITHIN THE PRESENTLY PLATTED AND DEVELOPED NEIGHBORHOOD COMMUNITY OF "WESTON AT WAKEFIELD" AND "WESTON II AT WAKEFIELD" AND WITHIN OTHER LAND AREAS LOCATED OUTSIDE OF THE YORKTOWN COMMUNITY THAT MAY BE ANNEXED OR MERGED INTO THE JURISDICTION OF THE ASSOCIATION, WHO ELECT IN WRITING TO JOIN THE ASSOCIATION, AND HAVE SUCH PRIVILEGES AND RIGHTS TO THE FULL USE AND ENJOYMENT OF THE COMMUNITY POOL AND IMPROVEMENTS LOCATED WITHIN RESERVE AREA "G" OF YORKTOWN PHASE I, AND OTHER CERTAIN YORKTOWN COMMUNITY COMMON AREAS AS SET FORTH OR TO BE SET FORTH BY THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION, SHALL BE SUBJECT TO ASSESSMENT BY THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION AT THE SAME FEE ASSESSMENT RATE AS RESIDENTIAL LOT OWNERS WITHIN THE OVERALL YORKTOWN COMMUNITY.

D. REQUIRED MOWING OF VACANT LOTS

THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION SHALL HAVE THE RIGHT, BUT NOT THE OBLIGATION, TO MOW ANY VACANT LOT WITHIN THE OVERALL YORKTOWN DEVELOPMENT COMMUNITY AFTER COMPLETION OF A 10 DAY NOTICE PERIOD TO THE LOT OWNER BY THE CITY OF JENKS CODE ENFORCEMENT DEPARTMENT THAT EFFECTIVELY STATES THAT SAID LOT IS IN VIOLATION OF SECTION 13-1-13, ABATEMENT OF WEEDS AND TRASH OF THE JENKS CITY CODE. THE YORKTOWN MASTER HOMEOWNERS ASSOCIATION SHALL HAVE THE RIGHT TO ADD COSTS OF SAID MOWING TO SAID LOT OWNER'S HOMEOWNERS ASSOCIATION DUES TO BE COLLECTED IN ACCORDANCE WITH SUBSECTION IV.C OF THIS SECTION.

SECTION V. ENFORCEMENT, DURATION, AMENDMENT, AND SEVERABILITY

A. ENFORCEMENT

THE RESTRICTIONS HEREIN SET FORTH ARE COVENANTS TO RUN WITH THE LAND AND SHALL BE BINDING UPON THE OWNERS, THEIR SUCCESSORS AND ASSIGNS. WITHIN THE PROVISIONS OF SECTION I. STREETS, EASEMENTS AND UTILITIES, AND SECTION II. PLANNED UNIT DEVELOPMENT RESTRICTIONS, ARE SET FORTH CERTAIN COVENANTS AND THE ENFORCEMENT RIGHTS PERTAINING THERETO, AND ADDITIONALLY THE COVENANTS WITHIN SECTION I AND II WHETHER OR NOT SPECIFICALLY THEREIN SO STATED, SHALL INURE TO THE BENEFIT OF THE OWNERS OF THE LOTS WITHIN YORKTOWN AND THE CITY OF JENKS AND SHALL BE ENFORCEABLE BY THE CITY OF JENKS, OKLAHOMA. IF THE UNDERSIGNED OWNER/DEVELOPER, OR ITS SUCCESSORS OR ASSIGNS OR OWNERS OF ANY LOTS WITHIN YORKTOWN SHALL VIOLATE ANY OF THE COVENANTS HEREIN, IT SHALL BE LAWFUL FOR THE CITY OF JENKS, ANY OWNER OF A LOT OR A PROPERTY OWNERS ASSOCIATION FORMED FOR THIS SUBDIVISION TO MAINTAIN ANY ACTION AT LAW OR IN EQUITY AGAINST THE PERSON OR PERSONS VIOLATING OR ATTEMPTING TO VIOLATE ANY SUCH COVENANT, TO PREVENT HIM OR THEM FROM SO DOING OR TO COMPEL COMPLIANCE WITH THE COVENANT IN ANY JUDICIAL ACTION BROUGHT BY A PROPERTY OWNERS ASSOCIATION OR AN OWNER OF A LOT WHICH ACTION SEEKS TO ENFORCE THE COVENANTS OR RESTRICTIONS SET FORTH HEREIN OR TO RECOVER DAMAGES FOR THE BREACH THEREOF, THE PREVAILING PARTY SHALL BE ENTITLED TO RECOVER REASONABLE ATTORNEYS FEES AND COSTS AND EXPENSES INCURRED IN SUCH ACTION.

B. DURATION

THESE RESTRICTIONS, TO THE EXTENT PERMITTED BY APPLICABLE LAW, SHALL BE PERPETUAL AND SHALL BE IN FORCE AND EFFECT FOR A TERM OF NOT LESS THAN THIRTY (30) YEARS FROM THE DATE OF THE RECORDING OF THIS DEED OF DEDICATION UNLESS TERMINATED OR AMENDED HEREINAFTER PROVIDED.

C. AMENDMENT

THE COVENANTS CONTAINED WITHIN SECTION I. STREETS, EASEMENTS AND UTILITIES MAY BE AMENDED OR TERMINATED AT ANY TIME BY A WRITTEN INSTRUMENT SIGNED AND ACKNOWLEDGED BY THE OWNER OF THE LAND TO WHICH THE AMENDMENT OR TERMINATION IS TO BE APPLICABLE AND APPROVED BY THE JENKS PLANNING COMMISSION, OR ITS SUCCESSORS WITH THE APPROVAL OF THE CITY OF JENKS, OKLAHOMA. THE COVENANTS WITHIN SECTION II. PLANNED UNIT DEVELOPMENT RESTRICTIONS, MAY BE AMENDED AT ANY TIME WITH 75 PERCENT AGREEMENT OF ALL OWNERSHIP IN YORKTOWN PHASE I, YORKTOWN PHASE I AMENDED, YORKTOWN PHASE I AMENDED II, YORKTOWN BLOCKS 10-12, AND OTHER PLATTED YORKTOWN COMMUNITIES, AS APPLICABLE, AND APPROVAL BY THE CITY OF JENKS PLANNING COMMISSION AND JENKS CITY COUNCIL. THE COVENANTS WITHIN SECTION III. PRIVATE BUILDING AND USE RESTRICTIONS, AND SECTION IV. HOMEOWNERS ASSOCIATION, MAY BE AMENDED OR TERMINATED AT ANY TIME WITH 75 PERCENT AGREEMENT OF ALL OWNERS WITHIN THAT NEIGHBORHOOD COMMUNITY THAT DESIRES THE CHANGE. THE PROVISIONS OF ANY INSTRUMENT AMENDING OR TERMINATING COVENANTS SHALL BE EFFECTIVE FROM AND AFTER THE DATE IT IS PROPERLY RECORDED.

D. SEVERABILITY

INVALIDATION OF ANY RESTRICTION SET FORTH HEREIN OR ANY PART THEREOF, BY AN ORDER, JUDGMENT, OR DECREE OF ANY COURT, OR OTHERWISE, SHALL NOT INVALIDATE OR AFFECT ANY OF THE OTHER RESTRICTIONS OR ANY PART THEREOF AS SET FORTH HEREIN, WHICH SHALL REMAIN IN FULL FORCE AND EFFECT.

IN WITNESS WHEREOF: YORKTOWN HOLDING, L.L.C., AN OKLAHOMA LIMITED LIABILITY COMPANY, HAS EXECUTED THIS INSTRUMENT THIS 26TH DAY OF SEPTEMBER, 2016.

YORKTOWN HOLDING, LLC
AN OKLAHOMA LIMITED LIABILITY COMPANY

BY Stephanie M. Love
MANAGER

STATE OF OKLAHOMA)

) SS.

COUNTY OF TULSA)

BEFORE ME, A NOTARY PUBLIC IN AND FOR SAID STATE AND COUNTY, ON THIS 26TH DAY OF SEPTEMBER, 2016, PERSONALLY APPEARED STEVE MURPHY TO ME KNOWN TO BE THE IDENTICAL PERSON WHO SUBSCRIBED THEIR NAME TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME, AS ITS MANAGER, THAT THEY EXECUTED THE SAME AS THEIR FREE AND VOLUNTARY ACT AND DEED, AND AS THE FREE AND VOLUNTARY ACT AND DEED OF SAID OKLAHOMA LIMITED LIABILITY COMPANY, FOR THE USES AND PURPOSE THEREIN SET FORTH.

Stephanie M. Love
STEPHANIE M. LOVE NAYLOR
MY COMMISSION EXPIRES: 3/2/2019
MY COMMISSION NUMBER: 15002084



CERTIFICATE OF SURVEY

I, ANDY FRITZ, OF FRITZ LAND SURVEYING, LLC, A LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OKLAHOMA UNDER CERTIFICATE OF AUTHORIZATION #5848, DO HEREBY CERTIFY THAT I HAVE CAREFULLY AND ACCURATELY SURVEYED, SUBDIVIDED, AND PLATTED THE TRACT OF LAND DESCRIBED ABOVE, AND THAT THE ACCOMPANYING PLAT DESIGNATED HEREIN AS "YORKTOWN BLOCKS 39-44", A SUBDIVISION IN THE CITY OF JENKS, TULSA COUNTY, STATE OF OKLAHOMA, IS A TRUE REPRESENTATION OF THE SURVEY MADE ON THE GROUND USING GENERALLY ACCEPTED PRACTICES, AND MEETS OR EXCEEDS THE MINIMUM TECHNICAL STANDARDS ADOPTED BY THE OKLAHOMA STATE BOARD OF LICENSURE FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS.

Andy Fritz
ANDY FRITZ
LICENSED PROFESSIONAL LAND SURVEYOR

OKLAHOMA NO. 1694

STATE OF OKLAHOMA)

) SS.

COUNTY OF TULSA)



BEFORE ME, A NOTARY PUBLIC IN AND FOR SAID STATE AND COUNTY, ON THIS 26TH DAY OF SEPTEMBER, 2016, PERSONALLY APPEARED ANDY FRITZ TO ME KNOWN TO BE THE IDENTICAL PERSON WHO SUBSCRIBED THEIR NAME TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME, AS ITS MANAGER, THAT THEY EXECUTED THE SAME AS THEIR FREE AND VOLUNTARY ACT AND DEED, AND AS THE FREE AND VOLUNTARY ACT AND DEED OF SAID OKLAHOMA LIMITED LIABILITY COMPANY, FOR THE USES AND PURPOSE THEREIN SET FORTH.

Jennifer Fritz
JENNIFER FRITZ
MY COMMISSION EXPIRES: 6/23/2018
MY COMMISSION NUMBER: 14005589

